



Gomersal Park Hotel, West Yorkshire

October 2001

Main Contractor: Lemmeleg Building & Contracting Ltd.

To facilitate excavation adjacent to an existing building, a contiguous minipile retaining wall was constructed. Piles were drilled into mudstone bedrock underlying the site, using rotary air flush techniques with temporary casing in the overburden strata. The piles were nominal 300mm diameter at 450mm centres and were 5.7 metres long. Reinforcement comprised full length API tube.